







NOZZLE SCHEDULE			
MARK	QTY	SIZE / RATING	DESCRIPTION
N1	1	2" 150# NPT	INLET
N2	1	2" 150# NPT	OUTLET
N3	2	1/2" 3000# NPT	PRESSURE GAUGE
N4	1	1/2" 3000# NPT	VENT
N5	1	2" 150# NPT	SPARE

VESSEL DESIGN CONDITIONS			
CODE: BEST COMMERCIAL PRACTICE			
M.A.W.P.:	150 PSI @ 250°F	GASKET:	BUNA
M.A.W.P.:	FV PSI @ 250°F		
M.D.M.T.:	-20° F @ 150 PSI		
HYDROTEST PRESS:	150 PSI		
MATERIAL:	SS316		

NOTES:

1. VESSEL DRY WEIGHT: 60.000 LBS.
2. SHIPPING WEIGHT: 120 LBS.
3. FLOODED WEIGHT: 107 LBS.
4. VESSEL VOLUME: 0.62 CU. FT.
5. VESSEL WILL HOUSE (QTY=1) SIZE ONE SS316 BASKET



SECTION K-K

APPROVED WITH MARK-UPS ☐

APPROVED ☐



THIRD ANGLE
PROJECTION
TOLERANCES-UNLESS
OTHERWISE NOTED
DECIMAL
X = ±.1"
XX = ±.02"
XXX = ±.005"
FRACTIONAL
X = ±1/8"
ANGULAR
= ± 1°
MAX. MACHINED
SURFACE FINISH
125/



FIL-TREK CORPORATION

55 Stafford Court
Cambridge, Ontario
N1T 1B3
Canada

Phone: (519) 623-7448
Fax: (519) 623-8807
Email: info@fil-trek.com
Website: www.fil-trek.com

THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED IN ANY WAY DETRIMENTAL TO THE CORPORATION

EQUIPMENT: ESL SERIES (SINGLE BAG FILTER VESSEL)

MODEL NO: S6ESL111-2P-CDB-150

CUSTOMER: STOCK

PARENT:
NONE

DRAWN: FZ

DATE:
1/29/2025

SERIAL No.

Part No.
002001-20038

REV. No.
0

CHK'D: TS

SCALE: NTS