




SECTION U-U
SCALE 1 : 12

NOZZLE SCHEDULE

MARK	QTY	SIZE / RATING	DESCRIPTION
N1	1	2" NPT CL3000	INLET
N2	1	2" NPT CL3000	OUTLET
N3	2	1/2" NPT CL3000	PRESSURE GAUGE
N4	1	1/2" NPT CL3000	VENT
N5	1	2" NPT CL3000	SPARE
N6	0		DIRTY DRAIN

VESSEL DESIGN CONDITIONS

CODE: ASME SECTION VIII DIV. 1, LATEST EDITION		
M.A.W.P.: 150 PSI @ 400°F	M.D.M.T.: -20°F @ 150 PSI	
M.A.W.P.: FV PSI @ 400°F	HYDROTEST PRESS: 210 PSI	
CORROSION ALLOWANCE: N/A	SERVICE: UNK. LIQUID, NON-LETHAL	
STAMP: UM/ CRN# L1521.1258	RADIOGRAPHY: N/A	
PWHT: N/A	GASKET: ☐ BUNA ☐ VITON ☐ EPDM ☐ OTHER: _____	
MATERIAL: SS304		
<u>NOTES:</u> DRY WEIGHT: 140 LBS SHIPPING WEIGHT: 170 LBS VOLUME: 1 CU. FT. INTERNALS: 1 X SIZE 2 BASKET	<u>FACTORY INSTALLED OPTIONS:</u> ☐ STAINLESS STEEL BOLTING (SS316) ☐ MESH LINED BASKETS: _____ MESH ☐ N3 DIAL PRESSURE GAUGE ☐ N3 DIFFERENTIAL PRESSURE GAUGE ☐ N3 DIFFERENTIAL PRESSURE GAUGE W/ SWITCH ☐ N4 VENT & GAUGE ASSEMBLY ☐ N4 VENT & GAUGE ASSEMBLY W/ AIR ELIMINATOR	
	☐ NSF CERTIFICATION ☐ ELECTROPOLISHED ☐ PICKLE AND PASSIVATION	



APPROVED WITH MARK-UPS ☐ APPROVED ☐



THIRD ANGLE PROJECTION
TOLERANCES-UNLESS OTHERWISE NOTED
DECIMAL .X = ±.1"
.XX = ±.02"
.XXX = ±.005"
FRACTIONAL .X = ±1/8"
ANGULAR = ± 1°
MAX. MACHINED SURFACE FINISH 125/√



FIL-TREK CORPORATION

55 Stafford Court
Cambridge, Ontario
N1T 1B3
Canada

Phone: (519) 623-7448
Fax: (519) 623-8807
Email: info@fil-trek.com
Website: www.fil-trek.com

THIS DRAWING IS THE PROPERTY OF 'FIL-TREK CORPORATION' AND MUST NOT BE COPIED OR USED IN ANY WAY DETRIMENTAL TO THE CORPORATION

EQUIPMENT: SL SERIES (BAG FILTER VESSEL)

MODEL NO: S4SL112-2P-CDB-150

CUSTOMER:

VESSEL QUANTITY:

DRWN / CHK: TP / NP
DATE: 2025-07-08

SERIAL No.

Part No. 002002-18547

SHEET GA

REV. No. 0